TECHNICAL MEMORANDUM

To: Eric Bowman **Date:** October 4, 2013

Environmental Quality Management

From: Brian Boyer cc: Project files

Patricia Hoch-Melluish Kieser & Associates, LLC

RE: Portage Creek Area Time Critical Removal Action

Project# 030281-0087

Yr-1 Vegetation Assessments

Introduction

Kieser & Associates, LLC (K&A) has been retained by Environmental Quality Management, Inc. (EQM) to provide professional services for re-vegetation monitoring (K&A Work Task 3) associated with the Portage Creek Area Time Critical Removal Action Project in Kalamazoo, Michigan. This technical memorandum summarizes the year-1 findings associated with re-vegetation monitoring.

A site location map depicting the location of each Portage Creek sediment removal work site, with respect to each other and local surrounding features, is provided as Figure 1. K&A efforts for re-vegetation monitoring included five sites that were completed in the fall of 2012. These sites included: SA-7, SA-6, SA-5D, SA-5 Axtell and SA-5C.

Work Summary and Findings

K&A personnel accessed each restored sediment removal work site on foot to assess the general condition of re-vegetation species present within the designated sediment removal work areas. These vegetation evaluation efforts were a qualitative assessment to monitor year-1 progress of re-vegetation, recommend corrective action, and presence of invasive species.

The first vegetation assessment was conducted in early summer on June 17, 2013 and the second vegetation assessment was conducted in late summer on September 16, 2013.

Field notes were recorded for each site to document plant species (seed and plugs), trees and shrubs that were previously part of each site restoration effort. Observed vegetation conditions, recommended corrective action and observed invasive species were documented for each site. Photograph documentation was also recorded to illustrate observed conditions. A copy of the June 17, 2013 vegetation assessment field notes is provided in Attachment A, and a copy of the September 16, 2013 vegetation assessment field notes is provided in Attachment B.

ATTACHMENT A

Year-1 Vegetation Monitoring
Observations, Recommendations and Photograph Documentation

June 17, 2013

KIESER & ASSOCIATES EQM Vegetation Progress Monitoring June 17, 2013 (Year 1-qualitative)

SA-5C

- Plug areas near Crosstown Parkway not thriving-weedy and dry. **May require some replacement plugs. Will reassess in late summer monitoring** (Photo 1).
- Crabapple tree on west side of creek not thriving or leafing out. **May require** replacement. Will reassess in late summer monitoring (Photo 2).
- All other trees and shrubs look healthy.
- East side turf grass very sparse, especially at the southern end (Photo 3). **Reseeding** is recommended.
- West side turf grass filling in well.
- Many invasive, weedy species establishing along east creek bank. (Purple loosestrife, curled dock, pokeweed, plantain, reed canary grass, stinging nettles, bindweed).
 Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.
- Many invasive, weedy species establishing along west creek bank. (Purple loosestrife curled dock, reed canary grass, nightshade, yellow iris) Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.

SA-5 Axtell Creek

- One flowering dogwood tree on north bank not thriving or leafing out (Photos 1 and 2). May require replacement. Will reassess in late summer monitoring.
- All other trees and shrubs look healthy.
- Existing mulberry tree on north bank has large downed limb. **Removal is recommended.**
- North side turf grass is establishing well with little to no sparse areas.
- Some invasive, weedy species establishing along north creek bank. (Purple loosestrife, curled dock). Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.
- Would recommend additional tree/shrub planting along south bank.

SA-5D

- Plug areas near Lake Street confluence not thriving-weedy and dry. **May require** some replacement plugs. Will reassess in late summer monitoring (Photos 1 and 2).
- Prairie seed mix sparse in a small area near Lake Street, west side creek (Photo 3).
 May require reseeding. Will reassess in late summer monitoring.
- East side turf grass south of Axtell Creek confluence very sparse (Photos 4 and 5). **Reseeding is recommended.**
- Plug areas near Axtell Creek confluence footbridge not thriving-weedy and dry. The areas are getting foot traffic and the plugs appear to be stepped on. **May require some replacement plugs. Will reassess in late summer monitoring** (Photos 6 and 7).

KIESER & ASSOCIATES EQM Vegetation Progress Monitoring June 17, 2013 (Year 1-qualitative)

- East side turf grass north of Axtell Creek confluence very sparse (Photo 8). **Reseeding is recommended.**
- Some invasive, weedy species establishing along west creek bank. (Purple loosestrife, curled dock, daisy fleabane, moth mullein, yellow sweet clover, creeping charley, nightshade, reed canary grass, pokeweed.) Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.
- Some invasive, weedy species establishing along east creek bank. (Purple loosestrife, curled dock, reed canary grass, giant ragweed, burdock, nightshade, stinging nettles, morning glory, daisy fleabane.) Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.
- All trees and shrubs look healthy.

SA-6

- Plug area near Stockbridge, west side of creek, well-tended and healthy (Photo 1).
- Could not find the three elderberry and two red-osier dogwoods near Stockbridge, east side of creek. **Installation of the five shrubs will be required.**
- All trees and shrubs that could be found look healthy.
- Prairie seed mix area sparse near Lake Street, west side of creek (Photo 2). May require reseeding. Will reassess in late summer monitoring.
- Some coir log slumping near Lake Street, east side of creek (Photos 3 and 4). Erosion doesn't appear to be a problem. Will reassess in late summer monitoring.
- Growth along both banks generally dense, but many invasive, weedy species present.
 (Purple loosestrife, curled dock, reed canary grass, buckthorn, thistle, moth mullein, cow vetch, yellow sweet clover, stinging nettles, nightshade, pokeweed.)
 Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.

SA-7

- Seeding is filling in well (Photo 1). Sparse in some areas, but overall good coverage. Will reassess in late summer monitoring.
- Some invasive, weedy species establishing on site. (Curled dock, yellow sweet clover, thistle, cow vetch, moth mullein.) Some management (weeding, herbicide) may be required. Will reassess in late summer monitoring.
- All spicebush plants appear to be struggling, but starting to leaf out (Photo 2). May require replacement. Will reassess in late summer monitoring.
- All other trees and shrubs look healthy.



Photograph 1: Plug area near Crosstown Parkway, east side of Portage Creek.



Photograph 2: Crabapple tree-poor leaf out, Crosstown Parkway, east side of Portage Creek.



Photograph 3: Bare turf grass area looking south from Vine Street, east side Portage Creek.





Photograph 1: Flowering dogwood tree – not thriving



Photograph 2: Flowering dogwood tree – not thriving



Photograph 1: Plug area near Lake Street, west side of Portage Creek.



Photograph 2: Plug area near Lake Street, east side of Portage Creek.





Photograph 3: Bare area looking south toward Lake Street, west side Portage Creek.



Photograph 4: Bare turf grass area looking north near Lake Street, east side Portage Creek.



Photograph 5: Bare turf grass area south of Axtell Creek confluence, east side of Portage Creek.



Photograph 6: Plug area looking north near Axtell Creek confluence, east side Portage Creek.





Photograph 7: Plug area north of Axtell Creek confluence, east side of Portage Creek.



Photograph 8: Turf grass area looking south near Axtell Creek confluence, east side Portage Creek.



Photograph 1: Plug area near Stockbridge Avenue, west side of Portage Creek.



Photograph 2: Prairie area looking south from Lake Street, west side Portage Creek.





Photograph 3: Prairie slope area near Lake Street, east side of Portage Creek.



Photograph 4: Coir log near Lake Street, east side Portage Creek.



Photograph 1: Prairie area near Reed Street, west side of Portage Creek.



Photograph 2: Spice bush-poor leaf out, west side Portage Creek.

ATTACHMENT B

Year-1 Vegetation Monitoring
Observations, Recommendations and Photograph Documentation
September 16, 2013

KIESER & ASSOCIATES

EQM Vegetation Progress Monitoring September 16, 2013 (Year 1-qualitative)

SA-5C

- Plug areas near Crosstown Parkway not thriving. May require some replacement plugs. Needs protection from foot traffic and maintenance during establishment period (Photo 1).
- Crabapple tree on west side of creek not thriving. **Will require replacement.** (Photo 2).
- One elderberry on west side of creek near Crosstown Parkway not thriving. (Photo 3). All other trees and shrubs look healthy. **Will reassess spring 2014.**
- East side turf grass still fairly sparse, especially at the southern end (Photo 4). It appears that a portion of the area to the north has been recently reseeded. **Additional reseeding is recommended.**
- Many invasive, weedy species establishing along both creek banks. (Purple loosestrife, curled dock, pokeweed, plantain, reed canary grass, stinging nettles, bindweed, ragweed, evening primrose, chicory). Some management (weeding, herbicide) may be required to control invasives.

SA-5 Axtell Creek

- Two flowering dogwood trees on north bank not thriving or leafing out (Photo 1). Will require replacement.
- One beech tree on north bank not thriving. All other trees and shrubs look healthy. Will reassess in spring 2014.
- Existing mulberry tree on north bank has large downed limb since early summer monitoring. **Removal is recommended.**
- North side turf grass is establishing well with little to no sparse areas.
- Plug area on north bank not thriving. (Photo 2). May require some replacement plugs. Needs protection from foot traffic and maintenance during establishment period.
- Many invasive, weedy species establishing along both creek banks. (Purple loosestrife, curled dock, pokeweed, buckthorn, honeysuckle). Some management (weeding, herbicide) may be required to control invasives.

SA-5D

- Plug areas near Lake Street not thriving. May require some replacement plugs. Needs protection from foot traffic and maintenance during establishment period (Photos 1 and 2).
- Prairie seed mix has filled in since early summer monitoring in a small area near Lake Street, west side creek.
- East side turf grass south of Axtell Creek confluence has filled in slightly since early summer monitoring, but still not very dense (Photos 3 and 4). **Reseeding is recommended.**
- Plug area south of Axtell Creek confluence footbridge not thriving. The area is getting foot traffic and the plugs appear to be stepped on. **May require some**

KIESER & ASSOCIATES

EQM Vegetation Progress Monitoring September 16, 2013 (Year 1-qualitative)

replacement plugs. Needs protection from foot traffic and maintenance during establishment period (Photos 5 and 6).

- Plug area north of Axtell Creek confluence footbridge beginning to establish. The area is getting foot traffic and the plugs appear to be stepped on. May require some replacement plugs. Needs protection from foot traffic and maintenance during establishment period (Photo 7)
- East side turf grass north of Axtell Creek confluence very sparse (Photo 8). **Reseeding is recommended.**
- Many invasive, weedy species establishing along creek banks. (Purple loosestrife, curled dock, giant ragweed, pokeweed, evening primrose, burdock.) Some management (weeding, herbicide) may be required to control invasives.
- Planting bed on east side near Crosstown Parkway looks good. **Maintenance** (weeding) may be required.
- Dogwood on west side of creek north of Axtell not thriving. All other trees and shrubs look healthy. **Will reassess in spring 2014**.

SA-6

- Plug area near Stockbridge, west side of creek, not thriving. **Will reassess in spring 2014.** (Photo 1).
- Could not find the three elderberry and two red-osier dogwoods near Stockbridge, east side of creek. **Installation of the five shrubs will be required.**
- All trees and shrubs that could be found look healthy.
- Prairie seed mix area filling in since early summer survey near Lake Street, west side of creek (Photo 2).
- No erosion areas observed along creek banks.
- Growth along both banks generally dense, but many invasive, weedy species present.
 (Purple loosestrife, curled dock, reed canary grass, buckthorn, thistle, moth mullein, cow vetch, yellow sweet clover, stinging nettles, nightshade, pokeweed.)
 Some management (weeding, herbicide) may be required to control invasives.
- Japanese knotweed reestablishing near Stockbridge on west side of creek.
 Management will be required.

SA-7

- Densely vegetated, but a little weedy. Invasives establishing onsite (spotted knapweed, pokeweed, stinging nettles, curled dock, white sweet clover, common ragweed, thistle) (Photo 1). Some management (weeding, herbicide) may be required to control invasives.
- Spicebush plants have recovered since the early summer survey and appear to be healthy (Photo 2).
- Rose bushes look a little weak-may be due to herbivory. Deer were observed on site. All other trees and shrubs look healthy.
- Downed limb across property (Photo 3). May need removal.



Photograph 1: Plug area near Crosstown Parkway, east side of Portage Creek.



Photograph 2: Crabapple tree-poor leaf out, Crosstown Parkway, west side of Portage Creek.





Photograph 3: Elderberry bush, not thriving, Crosstown Parkway, west side of Portage Creek.



Photograph 4: Bare turf grass area looking north from Crosstown Parkway, east side Portage Creek.





Photograph 1: Flowering dogwood tree – needs replacement



Photograph 2: Plug area north side of creek



Photographs taken at Axtell\Creek site SA-Axtell on September 16, 2013 by Patty Hoch-Melluish of Kieser & Associates, LLC.



Photograph 1: Plug area near Lake Street, west side of Portage Creek.



Photograph 2: Plug area near Lake Street, east side of Portage Creek.



Photograph 3: Bare turf grass area looking north near Lake Street, east side Portage Creek.



Photograph 4: Bare turf grass looking south in the area south of Axtell Creek confluence, east side of Portage Creek.



Photograph 5: Plug area near Axtell Creek confluence, east side Portage Creek.



Photograph 6: Plug area looking north near Axtell Creek confluence, east side Portage Creek.



Photograph 7: Plug area north of Axtell Creek confluence, east side of Portage Creek.



Photograph 8: Turf grass area looking north near Axtell Creek confluence, east side Portage Creek.



Photograph 1: Plug area near Stockbridge Avenue, west side of Portage Creek.



Photograph 2: Prairie area looking south from Lake Street, west side Portage Creek.



Photograph 1: Prairie area near Reed Street, west side of Portage Creek.



Photograph 3: Downed limb, west side of Portage Creek.



Photograph 2: Spice bush, west side Portage Creek.



Site

Location


KALAMAZOO COUNTY, MICHIGAN

TES \checkmark SSOCI ER S

EQM CONTACT

Environmental Quality Management 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-265-8875 Mr. Eric Bowman

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave. Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.








ESER ASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA- I A



INDEX OF DRAWING SHEETS

- **Cover Sheet**
- Site SA-1A Vegetation Plan
- 3 **Detail Drawings**
- **Detail Drawings**
- Quantities
- 6-8 Specifications

SITE LOCATION MAP

CITY OF KALAMAZOO http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan,



Know what's below. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE
INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT


NOTE TO CONTRACTOR: 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL.
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. With EPA oversight, Contractor is not required to obtain permits for re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.



ECOLOFENCE 24 BY PRICE & COMPANY

FRONT VIEW

- SPACING 6' MAX. -

SILT FENCE A

SILT FENCE B

6" ANCHOR TRENCH

SOCL S ER

IATES



NOTES:

1. ON-CENTER PLANT SPACING INDICATED ON PLANTING PLAN.
2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

- EROSION BLANKET INSTALLED BEFORE PLANTING


PROFILE


PLANTING


GROUNDCOVER - NO SCALE

SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE











FIGURE

Portage Creek Area Time Critical Removal Action
KALAMAZOO, MI
EQM Project Number: 030281.0087

536 E. MICHIGAN AVE., SUITE 300 KALAMAZOO, MI 49007 ph: (269) 344-7117 fax: (269) 344-2493

SER RASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

ER

Area #1 - Plugs (City Property next to Bridge)

Theam I had terry here to shade			
Common Name	Scientific Name	QTY.	<u>UNIT</u>
Threadleaf coreopsis	Coreopsis verticillata	10	EA
Black eyed susan	Rudbeckia hirta	10	EA
Smooth penstemon	Penstemon digitalis	10	EA
Prairie dropseed	Sporobolus heterolepis	10	EA
Prairie blazingstar	Liatris pycnostachya	10	EA
Butterfly weed	Asclepias tuberosa	10	EA

AREA #2 - PLANTS

City of Kalamazoo Rose Park Ornamental Garden Plan 2013

Plant Quantities and Specifications

14-one gallon ANEMONE-White

Honorine Joberit

3'-3 1/2' Height

1 1/2' Spread August

25 - one gallon DAYLILY-Red

Pardon Me

1 ½' Height

1' Spread

July/August

15 - one gallon DELPHINIUM-Blue

Blue Bird

4'-6' Height

2'-3' Spread

June

18 - one gallon DIGITALIS-MIX

Foxy Mix

1 1/2'-3' Height

1 1/2' Spread

July

30 - one gallon ECHINACEA-Red

Sombrero Salsa Red 22"-2' Height

1'-2' Spread

June-August

21 - one gallon HEUCHERA-Red

Autumn Leaves

8"-1' Height

1'-1 1/2' Spread

6 - one gallon HOSTA-Variegated

Patriot

1'-3' Height

1'-3' Spread

June/July

7 - one gallon LIATRIS-White

Spicata Alba

3'-4' Height

1'-2' Spread

July/August

8- one gallon LUPINE-White

Noble Maiden

2'-3' Height

2' Spread

June

8 - one gallonPENNISETUM-Red

Red Head

3'-4' Height 3' Spread

July/August

8 - one gallon PLATYCODON-White Fuji White

1'-2' Height 1 1/2' Spread

June/July

July-August

QTY. UNIT ITEM DESCRIPTION AC SOIL ROUGHENING/SCARIFICATION 2.01 NATIVE SEED MIX (WP-7) 0.1 AC NATIVE SEED MIX (DP-4) 0.12 AC "NO-MOW" LAWN MIX 0.83 AC AC "TYPE-A" LAWN MIX 0.13 **DS75 MULCH BLANKET** AC 0.31 **CYPRESS SHREDDED MULCH** 33 CYD 200 RYERSON STEEL EDGING LFT **CONCRETE SIDEWALK** 510 SFT WHITE OAK 4 EΑ RED MAPLE 3 EΑ SILVER MAPLE EΑ 1 RIVERBIRCH (MULTI-STEM) 3 EΑ REDBUD (1 MULTI-STEM) 5 EΑ SERVICEBERRY EΑ 1 SWAMP WHITE OAK 1 EΑ NINEBARK 🛞 7 EΑ KALM'S ST JOHN'S WORT 🏶 3 EΑ SHADBLOW SERVICEBERRY 🌕 5 EΑ RED-OSIER DOGWOOD 🧶 29 EΑ

QUANTITIES (SA-1A)

Area #3 - Plugs (Starworld Property)

Common Name	Scientific Name	QTY.	<u>UNIT</u>
Threadleaf coreopsis	Coreopsis verticillata	40	EA
Black eyed susan	Rudbeckia hirta	40	EA
Smooth penstemon	Penstemon digitalis	39	EA
Prairie dropseed	Sporobolus heterolepis	39	EA
Prairie blazingstar	Liatris pycnostachya	39	EA
Butterfly weed	Asclepias tuberosa	39	EA
	Symphyotrichum novae		
New England aster	angliae	39	EA

Area #4 - Plugs (Tool & Die Property along Tracks)

Common Name	Scientific Name	QTY.	<u>UNIT</u>
Threadleaf coreopsis	Coreopsis verticillata	36	EA
Black eyed susan	Rudbeckia hirta	36	EA
Smooth penstemon	Penstemon digitalis	36	EA
Prairie dropseed	Sporobolus heterolepis	36	EA
Prairie blazingstar	Liatris pycnostachya	36	EA
Butterfly weed	Asclepias tuberosa	35	EA
	Symphyotrichum novae		
New England aster	angliae	35	EA

SER

SA-1A VEGETATION

PART 1. GENERAL

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding.
- C. Seed protection on slopes.
- Planting special seed mixes.
 - 1. WP-7 (Short Stature Bioswale Mix)
 - 2. DP-4 (Short Grass Prairie Erosion Control Seed Mix)
 - 3. "No-Mow" Lawn Mix (6 Blend Custom Fescue Mix)
 - 4. "Type-A" Lawn Mix (General Turf Grass Lawn Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - 1. Submit seed tags to Engineer prior to seeding.
 - 2. Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Topsoil
 - Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed to achieve min. 6 inches depth for upland areas to minimize weed seed viability.
- Water
 - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

Portage Creek Area Time Critical Removal Action FQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page I

2.03 SEED MIXTURES

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Chad Hughson

Contact: Cheryl Tolley

Contact: Trish Hacker-Henning

14921 Hand Road

Fort Wayne, Indiana 46818 Ph; (260) 489-8511 Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Great Lakes Landscape Supply

15200 Cedar Springs Ave NE Cedar Springs, MI 49319 Ph: (616) 696-5665 Fax: (616) 696-5785

Email: info@greatlakeslandscapesupply.com

3) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

4) Hidden Savanna Nursery

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

5) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462 Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

6) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page 2

SER

Special Native Seed Mixes

Short Stature Bioswale Mix (WP-7)

Approximate mix weight 72 lb/acre with 68 native seeds/sq. ft. 63.5% Grasses/Sedges/Rushes; 36.5% Forbs

Scientific Name	Common Name	Percent of Mix Category
Grasses, Sedges, and Rushes		
Calamagrostis canadensis	Blue Joint Grass	22.71%
Carex frankii	Frank's Sedge	2.99%
Carex granularis	Meadow Sedge	1.97%
Carex normalis	Spreading Oval Sedge	12.24%
Carex shortiana	Short's Sedge	2.84%
Carex stipata	Stalk Grain Sedge	1.81%
Carex tribuloides	Blunt Broom Sedge	12.24%
Carex vulpinoidea	Fox Sedge	11.68%
Elymus virginicus	Virginia Wild Rye	17.95%
Leersia oryzoides	Rice Cut Grass	13.57%
Total		100.00%
Forbs		
<u>Bidens cermia</u>	Nodding Bur Marigold	7.29%
Echinacea purpurea	Purple Coneflower	1.91%
Euthamia graminifolia	Flat-top Fragrant Goldenrod	8.07%
Gentiana andrewsii	Fringe-top Bottle Gentian	14.88%
Lobelia siphilitica	Great Blue Lobelia	2,26%
Penstemon digitalis	Foxglove Beardtongue	17.59%
Pycnanthemum virginianum	Mountain Mint	17.10%
Rudbeckia fulgida	Showy Black-eyed Susan	2.84%
Rndbeckia hirta	Black-eyed Susan	23.24%
Tradescantia ohiensis	Ohio Spiderwort	0.88%
Verbena strictu	Hoary Vervain	2.92%
Zizea aurea	Golden Alexanders	1.01%
Total		100.00%
Temporary Cover Grasses		
Agrostis alba	Redtop	72.55%
Avena sativa	Seed Oats	6.05%
Lolium multiflorum	Annual Rye Grass	21.40
Total	-	100.00%

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

2) Short Grass Prairie Erosion Control Seed Mix (DP-4)

Approximate mix weight 87 lb/acre with 107 native seeds/sq. ft. 66.6% Grasses/Sedges/Rushes; 33.4% Forbs

Scientific Name	Common Name	Percent of Mix Category
Grasses, Sedges, and Rushes		
Bouteloua curtipendula	Side Oats Grama	14.83%
<u>Carex bicknellii</u>	Bicknell's Sedge	1.52%
Elvnus virginicus	Virginia Wild Ryc	17.54%
Schizachyrium scoparium	Little Bluestem	66.11%
Total		100.00%
Forbs		
Asclepias syracia	Common Milkweed	0.51%
Coreopsis lanceolata	Sand Corcopsis	15.41%
Echinacea purpurea	Purple Coneflower	2.67%
Penstemon digitalis	Foxglove Beard Tongue	10.99%
<u>Rudbeckia hirta</u>	Black-eyed Susan	43.36%
Solidago nemoralis	Gray Goldenrod	9.02%
<u>Verbena stricta</u>	Hoary Vervain	16.34%
<u>Zizia aurea</u>	Golden Alexanders	1.70%
Tetal		100.00%
Temporary Cover Grasses		
Agrostis alba	Red Top	72.55%
Avena sativa	Seed Oats	6.05%
Lolium multiflorum	Annual Rye Grass	21.40%
Total		100.00%

3) "No-Mow" Lawn Mix

Prairie Nursery P.O. Box 306 Westfield, WI 53964 Ph: (800) 476-9453

Fax: (608) 296-2741

E-mail: cs@prairienursery.com www.prairienursery.com

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

ER

4) "Type-A" Seed Mixture (Repair of Turf Grass Lawn Areas)

- 25 % Famous Kentucky Bluegrass
- 25% Baron Kentucky Bluegrass
- Secretariat Perennial Ryegrass
- 30% Boreal Creeping Red Fescue
- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be rough graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions.

3.02 SEEDING & FERTILIZING

- Contractor shall broadcast seed all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed shall be applied to all Repair Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the Repair Areas.

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Page 5

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

Hanes Geo Components

Contact: Mark Cavanaugh 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

Email: mark.cavanaugh@hanescompanies.com

- Minimum Erosion Control Products (as specified on the drawings).
 - Straw Single Net Erosion Blankets (100% biodegradable).
 - TerraTex HPG-44 Geotextile Fabric
 - 3. Ecolofence 24" Silt Fence
- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and A. planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920


KIESER & ASSOCIATES, LLC


ER

EQM CONTACT **Environmental Quality Management** 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-265-8875

Mr. Eric Bowman

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave. Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.









ESER ASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA-IC

INDEX OF DRAWING SHEETS

- **Cover Sheet**
- Site SA-1C Vegetation Plan
- **Detail Drawings**
- Specifications

o Ave 94 43 **PROJECT AREA**

SITE LOCATION MAP

CITY OF KALAMAZOO http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan.



Know what's below. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT

3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:


- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. With EPA oversight, Contractor is not required to obtain permits for re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.

FULL SCALE: 1" = 30



PREPARE SEEDBED, ROUGH GRADE, PLACE SEED

INSTALL MULCH EROSION BLANKETS



- SPACING 6' MAX. -

SILT FENCE A


SILT FENCE B 7

6" ANCHOR TRENCH

IATES ENGINEERING ER S



- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF SEED.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER PINNING.
- 4. THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.
- 5. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 6" OVERLAP, STAPLE THROUGH OVERLAPPED AREA. APPROXIMATELY 12" APART.
- BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.
- LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.



SOIL EROSION CONTROL GEOTEXTILE SILT FENCE

FENCE POSTS DRIVEN INTO GROUND 1' MIN.-

1' MIN.

FRONT VIEW

UNDISTURBED SOILS

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, ' TOWARDS DISTURBED SOILS.

COMPACT ANCHOR TRENCH

FABRIC TO BE WRAPPED AROUND FENCE POST

SHEET FLOW

SILT FENCE A


FENCE B

FENCE JOINT


EROSION CONTROL BLANKET DETAIL NO SCALE

RUBBER HOSE AT CONTACT POINTS TWICE RADIUS OF ROOT BALL 4" MINIMUM PINE STRAW BERM SIZE TO BE PROMINENT COMPACT OUTER EDGE WITH FOOTPRINT GROUND TREATED STAKES
(3 STAKES SPACED EQUIDISTANT) PEEL BACK BURLAP BACK FILL 1 PART COMPOST WITH 5 PARTS EXISTING SOIL - COMPACT BACK FILL IN BOTTOM OF HOLE STAKING AND PLANTING

TREE DETAIL NO SCALE







PLANTING GROUNDCOVER - NO SCALE

S

SA-1C VEGETATION

PART 1. **GENERAL**

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- В. Seeding.
- C. Seed protection on slopes.
- Planting special seed mixes. D.
 - 1. DP-3 (Short Stature Prairie Seed Mix)
 - 2. WS-2 (Riparian Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - Submit seed tags to Engineer prior to seeding.
 - Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging, Damaged packages are not acceptable.

1.05 EXISTING CONDITIONS

A. Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

2.01 GROWING MEDIA

- Topsoil A.
 - 1. Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed to minimize weed seed viability.
- - To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281,0087 Specifications 02920

KIESER & ASSOCIATES, LLC

2.03 SEED MIXTURE

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Chad Hughson

Contact: Cheryl Tolley

Contact: Randy Counterman

KIESER & ASSOCIATES, LLC

Contact: Trish Hacker-Henning

14921 Hand Road

Fort Wayne, Indiana 46818

Ph: (260) 489-8511

Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142

E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery

18 N Van Kal Street Kalamazoo, MI 49009 Ph; (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

6) Native Landscapes

28092 M-40 Hwy. Paw Paw, MI 49079 Phone: 269-929-3455

Email: randy.counterman@gmail.com

Page 2

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

Special Native Seed Mixes

Midwestern Short Stature Prairie Seed Mix (DP-3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientific Name	Common Name
Grasses, Sedges, and	Rushes
Bouteloua curtipendula	Side Oats Grama
Carex bicknellii	Bicknell's Sedge
Elymus virginicus	Virginia Wild Rye
Schizachyrium scoparium	Little Bluestem
Sporobolus heterolepis	Prairie Dropseed

Forbs

4 0100	
Asclepias syriaca	Common Milkweed
Asclepias tuberosa	Butterfly Milkweed
Aster ericoides	White Heath Aster
Coreopsis lanceolata	Sand Coreopsis
Corcopsis palmata	Prairie Coreopsis
Echinacea purpurea	Purple Coneflower
Gentiana andrewsii	Fringe-top Bottle Gentian
Helianthus occidentalis	Few-leaf Sunflower
Lespedeza capitata	Round-headed Bushclover
Liatris aspera	Rough Blazingstar
Liatris scariosa nieuwlandii	Savanna Blazingstar
Lupinus perennis	Wild Blue Lupine
Parthenium integrifolium	Wild Quinine
Penstemon digitalis	Foxglove Beard Tongue
Petalostemum purpureum	Purple Prairie Clover
Potentilla arguta	Tall Cinquefoil
Pycnanthemum virginianum	Mountain Mint
Rudbuckia fulgida	Showy Black-eyed Susan
Rudbeckia hirta	Black-eyed Susan
Solidago nemoralis	Gray Goldenrod
Tradescantia ohiensis	Ohio Spiderwort
Verbena stricta	Hoary Vervain

Temporary Cover Grasses

Zizia aurea

Portage Creek Area Time Critical Removal Action

Avena sativa Seed Oats

Midwestern Riparian Seed Mix (WS-2)

Approximate mix weight 73 lb/acre with 46 native seeds/sq. ft. 13.9% Grasses/Sedges/Rushes; 5.4% Forbs; 80.7% Temporary Cover Grasses

*SPECIAL NOTES: Please incorporate Carex stricta and Carex bebbil into seed mix. Substitute Giant St. John's Wort (Hypericum ascron) for Wingstem (Verbesina alternifolia).

Grasses, Sedges, and	l Rushes
Carex frankii	Frank's Sedge
Carex muskingumensis	Palm Sedge
Carex normalis	Soreading Oval Sede

Common Name

Care Carex squarrosa Squarrose Sedge Carex vulpinoidea Fox Sedge Cinna arundinacea Common Wood Reed Elymus canadensis Canada Wild Rye Elymus riparius Riverbank Wild Rye Virginia Wild Rye Elymus virginicus Glyceria striata Fowl Manna Grass Rice Cut Grass Leersia oryzoides Switch Grass Panicum virgatum Scirpus atrovirens Dark Green Bulrush

Scirpus pendulus Drooping Bulrush

Forbs

Lolium multiflorum

Scientific Name

2)

Aster novae-angliae New England Aster Bidens cernua Nodding Bur Marigold Eupatorium purpureum Purple Joe Pye Weed Eupatorium rugosum White Snakeroot Heliopsis helianthoides False Sunflower Fringed Loosestrife Lysimachia ciliata Rudbeckia laciniata Green-headed Coneflower Rudbeckia triloba Brown-eyed Susan

Cup Plant Silphium perfoliatum

Verbesina alternifolia Wingstem (substitute Giant St. John's Wort) Vernonia gigantea Tall Ironweed

Annual Rye Grass

KIESER & ASSOCIATES, LLC

Golden Alexanders Zizia aurea

Temporary Cover Grasses

Agrostis alba Redtop

Agrostis alba palustris Creeping Bent Grass Avena sativa Seed Oats

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

Golden Alexanders

SER

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture. C.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be rough graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions.

3.02 SEEDING & FERTILIZING

- Contractor shall broadcast seed all topsoiled restoration areas at the rates recommended Α. by the seed supplier for each type of native seed mix specified.
- Seed shall be applied to all Repair Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the Repair Areas.

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Hanes Geo Components

425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230

Fx: (616) 530-2317 Portage Creek Area Time Critical Removal Action

EOM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

Contact: Mark Cavanaugh

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. Straw Single Net Erosion Blankets (100% biodegradable).
 - 2. TerraTex HPG-44 Geotextile Fabric
 - 3. Ecolofence 24" Silt Fence
- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EOM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of Α. vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

ER

EQM CONTACT

Environmental Quality Management 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-265-8875 Mr. Éric Bowman

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave, Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.










PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087 PORTAGE CREEK - SITE SA-5A



INDEX OF DRAWING SHEETS

- **Cover Sheet**
- Site SA-5A Vegetation Plan
- **Detail Drawings**
- Specifications

SITE LOCATION MAP

CITY OF KALAMAZOO http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan.



Know what's below. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT

3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- 7. SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. No permitting is required for conducting re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.

Scientific Name

Allium cercuum

Asclepias syriaca

Aster novae-angliae

Echinacea purpurea

Scutellaria lateriflora

Trandescantia ohioensis

Solidago riddelli

Coreoposis lanceloata

Area #1 - Plugs

Common Name

Knodding pink onion

Common milkweed

New England aster

Purple coneflower

Mad-dog skullcap

Spiderwort

Riddel's goldenrod

Sand coreopsis

TE SOCI S ER S

Area #3 - Plugs Scientific Name QTY. UNIT Common Name 14 EA Knodding pink onion Allium cercuum Asclepias tuberosa 14 Butterfly weed Coreoposis lanceloata 14 Sand coreopsis EA Purple coneflower Echinacea purpurea 14 EA Great blue lobelia Lobelia siphilitica 14 EA Rudbeckia fulgida 14 EA Black-eyed susan 14 EA Spiderwort Trandescantia ohioensis Verbena hastata 13 EA Blue vervain

Area #2 - Plugs QTY. UNIT Common Name Scientific Name 14 EA Knodding pink onion Allium cercuum Common milkweed 14 EA Asclepias syriaca New England aster Aster novae-angliae 14 EA 14 EA Crooked stem aster Aster prenanthoides 14 Purple coneflower Echinacea purpurea EA Marsh blazingstar Liatric spicata 13 EA Great blue lobelia Lobelia siphilitica 13 EA 13 EA Lupinus perennis Interruppted fern Osmundia claytoniana 13 EA Solidago riddelli 13 Riddel's goldenrod EA EA

E. Walnut St.

EXISTING ASPHALT

NEW FENCE

TYPE "A" LAWN MIX (WEST OF FENCE (1,200 SFT)

46 ACRES

MIX OF VEGETATIVE PLUGS (1,105 FT2, 276 PLUGS, 2' O.C.)

RED MAPLE (3) NEW DRAINAGE STRUCTURE

QUANTITIES (THIS SHEE	T)	
ITEM DESCRIPTION	QTY.	UNIT
SOIL ROUGHENING/SCARIFICATION	0.46	AC
NATIVE SEED MIX (DP-3)	0.46	AC
TURF GRASS RESTORATION	1,200	SFT
DS75 MULCH BLANKET	0.49	AC
RED MAPLE	5	EA
REDBUD 🛠	4	EA
FLOWERING DOGWOOD	2	EA
WILD CRAB APPLE	1	EA
RED-OSIER DOGWOOD *	5	EA
COMMON NINEBARK *	5	EA
ELDERBERRY 0	5	EA

REFERENCE:

MANUAL, APRIL 2006

ALL TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE COORDINATED WITH THE PERMANENT CONTROL MEASURES TO ASSURE EFFECTIVE CONTROL OF SEDIMENTS DURING CONSTRUCTION OF THE PROJECT.

MDOT SOIL EROSION AND SEDIMENT CONTROL

SOIL EROSION & SEDIMENT CONTROL NOTES:

PERMANENT/TEMPORARY SEEDING

VEGETATIVE BUFFER AT WATERCOURSE

INLET PROTECTION GEOTEXTILE AND STONE

SOIL ROUGHENING AND SCARIFICATION

TREES, SHRUBS AND PERENNIALS


SILT FENCE

MULCH BLANKETS

ALL TEMPORARY EROSION CONTROL DEVICES SHALL BE REMOVED AFTER VEGETATION HAS BEEN ESTABLISHED OR AT THE DISCRETION OF THE ENGINEER. THE CONTRACTOR SHALL TAKE CARE DURING REMOVAL TO MINIMIZE SEDIMENT IMPACT TO NEARBY SURFACE WATER FEATURES.

SOIL DISTURBANCE/REPAIR SEQUENCE:

INSTALL EROSION CONTROLS PREPARE SEEDBED, FINE GRADE, PLACE SEED INSTALL MULCH EROSION BLANKETS



NOTES:

SHRUBS TO BE 3-GALLON SIZE. TREES TO BE 2" CALIPER, 6-8' TALL, BALLED/BURLAP

THE SHEEDSON

APPROX. SCALE (FT) FULL SCALE: 1" = 100' EA EA EA

UNIT

EA

EA

EA

EA

EA

16

16

16

16

16

16

16

16

13 Trandescantia ohioensis

Spiderwort

16 AREAS #1 & #2

EXISTING

MIX OF VEGETATIVE PLUGS (445 FT2, 111 PLUGS, 2' O.C.)

EXIST. FENCE PROTECT NEW GUARDRAIL PORTAGE

VEGETATIVE BUFFER DP-3 MIX

EXISTING PARKING

APPROX.
RE-VEGETATION
WORK LIMITS

PROVIDE 1-YR WARRANTY ON ALL TREES/SHRUBS

- SPACING 6' MAX. -

SILT FENCE A

SILT FENCE B **5**

6" ANCHOR TRENCH

TE SO S T)



PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF FERTILIZER AND SEED.


. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER PINNING.

THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.

WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 6" OVERLAP, STAPLE THROUGH OVERLAPPED AREA. APPROXIMATELY 12" APART.

BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.

. LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.





1' MIN.

FRONT VIEW

FENCE POSTS DRIVEN INTO GROUND 1' MIN.

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, TOWARDS DISTURBED SOILS.

COMPACT ANCHOR TRENCH

FABRIC TO BE WRAPPED AROUND FENCE POST

SHEET FLOW

SECTION VIEW


FENCE B


FENCE JOINT

SILT FENCE A


UNDISTURBED SOILS











PLANTING GROUNDCOVER - NO SCALE

ER

50

SA-5A VEGETATION

PART 1. **GENERAL**

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding and fertilizing.
- C. Seed protection on slopes.
- D. Hydroseeding.
- Planting special seed mixes
 - 1. DP-3 (Midwestern Short Stature Prairie Seed Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - Submit seed tags to Engineer prior to seeding.
 - 2. Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.
- Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. **PRODUCTS**

GROWING MEDIA 2.01

- Topsoil
 - 1. Existing topsoil shall be re-used.
 - Import additional topsoil as needed.
- - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

2.03 SEED MIXTURE

Type "A" Seed Mixture (Repair of General Lawn Areas)

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

Page I

25 % Famous Kentucky Bluegrass Baron Kentucky Bluegrass Secretariat Perennial Ryegrass Boreal Creeping Red Fescue

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

14921 Hand Road Fort Wayne, Indiana 46818

Ph; (260) 489-8511 Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph; (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery Contact: Chad Hughson

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph; (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Saudhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

6) Mary Ann's Michigan Trees & Shrubs

28092 M-40 Hwv. Paw Paw, MI 49079 Phone: (269) 628-2474 Email: mamenck@mei.net

EOM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Trish Hacker-Henning

Contact: Cheryl Tolley

Contact: Mary Ann Menck

Portage Creek Area Time Critical Removal Action

Page 2

ER

S

S

Special Native Seed Mixes G.

Midwestern Short Stature Prairie Seed Mix (DP3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientific Name	Common Name		
Grasses, Sedges, and	Rushes		
Bouteloua curtipendula	Side Oats Grama		
Carex bicknellii	Bicknell's Sedge		
Elymus virginicus	Virginia Wild Rye		
Schizachyrium scoparium	Little Bluestem		
Sporobolus heterolepis	Prairie Dropseed		
Forbs			
Asclepias syriaca	Common Milkweed		
Asclepias tuberosa	Butterfly Milkweed		
Aster ericoides	White Heath Aster		
Coreopsis lanceolata	Sand Coreopsis		
Coreopsis palmata	Prairie Coreopsis		
Echinacea purpurea	Purple Coneflower		

Gentiana andrewsii Fringe-top Bottle Gentian Helianthus occidentalis Few-leaf Sunflower Round-headed Bushclover Lespedeza capitata Rough Blazingstar Liatris aspera Liatris scariosa nieuwlandii Savanna Blazingstar Wild Blue Lupine Lupinus perennis Parthenium integrifolium Wild Quinme Penstemon digitalis Foxglove Beard Tongue Petalostemum purpureum Purple Prairie Clover Potentilla arguta Tall Cinquefoil

Pycnanthemum virginianum Mountain Mint Rudbuckia fulgida Showy Black-eyed Susan Rudbeckia hirta Black-eved Susan Solidago nemoralis Gray Goldenrod Tradescantia ohiensis Ohio Spiderwort

Hoary Vervain Verbena stricta Zizia aurea Golden Alexanders

Temporary Cover Grasses

Avena sativa Seed Oats

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be fine graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All

Page 3

Portage Creek Area Time Critical Removal Action EOM Project Number: 030281,0087

Specifications 02920

KIESER & ASSOCIATES, LLC

windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions. The entire surface shall be finished to provide positive drainage.

3.02 SEEDING & FERTILIZING

- Contractor shall sew seed and fertilize all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed and fertilizer shall be applied to all General Repair Areas and Spoil Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the General Repair Areas and Stockpile Areas.
 - a. Seed at 350 pounds per acre
 - b. Fertilize at 500 pounds per acre of 12-12-12

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Hanes Geo Components

Contact: Mark Cavanaugh 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

- Minimum Erosion Control Products (as specified on the drawings).
 - Straw Single Net Erosion Blankets (100% biodegradable).
 - 2. TerraTex HPG-44 Geotextile Fabric
 - Ecolofence 24" Silt Fence

Portage Creek Area Time Critical Removal Action FOM Project Number: 030281.0087 Specifications 02920

Page 4

- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from crosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Site

Location

KALAMAZOO COUNTY, MICHIGAN

in Kalamazoo County, Michigan,

SER

EQM CONTACT Environmental Quality Management

18000 Carillon Boulevard Cincinnati, OH 45240 (513)-309-4703 Mr. Jeff Rhinefield

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave. Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.







PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087 PORTAGE CREEK - SITE SA-5C & D, AXTELL

INDEX OF DRAWING SHEETS

- **Cover Sheet**
- Site SA 5-C&D, Axtell Vegetation Plan
- **Detail Drawings**
- Specifications



SITE LOCATION MAP

CITY OF KALAMAZOO http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22



Know what's below. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE
INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT


NOTE TO CONTRACTOR: 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. No permitting is required for conducting re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.



ECOLOFENCE 24 BY PRICE & COMPANY.

- SPACING 6' MAX.

SILT FENCE A

SILT FENCE B

6" ANCHOR TRENCH

FENCE POSTS DRIVEN INTO GROUND 1' MIN.

1' MIN.

SOIL EROSION CONTROL

GEOTEXTILE SILT FENCE

FRONT VIEW

SOC ER

- PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF FERTILIZER AND SEED.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER PINNING.
- THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.
- WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 6" OVERLAP, STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART.
- BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.
- LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.

OVERLAP TO BE SHINGLED WITH DIRECTION OF CREEK FLOW DIRECTION OF FLOW

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, TOWARDS DISTURBED SOILS.

COMPACT ANCHOR TRENCH

ON UPHILL SIDE OF FILTER FABRIC

FABRIC TO BE WRAPPED AROUND FENCE POST

SHEET FLOW

SILT FENCE A

FENCE JOINT


UNDISTURBED SOILS

EROSION CONTROL BLANKET DETAIL

NO SCALE

RUBBER HOSE AT CONTACT POINTS UNTIE BALLING STRING FROM BASE OF TRUNK TWICE RADIUS OF ROOT BALL 4" MINIMUM PINE STRAW OR BARK MULCH GROUND TREATED STAKES
(3 STAKES SPACED EQUIDISTANT) PEEL BACK BURLAP BACK FILL 1 PART COMPOST WITH 5 PARTS EXISTING SOIL COMPACT BACK FILL IN BOTTOM OF HOLE STAKING AND PLANTING

TREE DETAIL





SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE PLANT SPACING AS PER PLAN - EROSION BLANKET INSTALLED BEFORE PLANTING PREVIOUS GROWING LEVEL AT FINISH GRADE **PROFILE**

PLANTING GROUNDCOVER - NO SCALE

NOTES:
1. ON-CENTER PLANT SPACING INDICATED IN GROUNDCOVER SCHEDULE (SHEET 9).

2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

<u>Plan</u>

SER

SA-5C&D, AXTELL VEGETATION

PART 1. **GENERAL**

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding and fertilizing.
- Seed protection on slopes. C.
- Hydroseeding. D.
- Planting special seed mixes
 - 1. DP-3 (Midwestern Short Stature Prairie Seed Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - 1. Submit seed tags to Engineer prior to seeding.
 - 2. Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.
- Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Toosoil
 - 1. Existing topsoil shall be re-used.
 - Import additional topsoil as needed.
- - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

2.03 SEED MIXTURE

Type "A" Seed Mixture (Repair of General Lawn Areas)

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page I

Famous Kentucky Bluegrass 25% Baron Kentucky Bluegrass Secretariat Perennial Ryegrass Boreal Creeping Red Fescue

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel 14921 Hand Road

Fort Wayne, Indiana 46818

Ph: (260) 489-8511 Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery Contact: Chad Hughson

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots Contact: Trish Hacker-Henning

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm Contact: Cheryl Tolley

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

6) Mary Ann's Michigan Trees & Shrubs

28092 M-40 Hwy. Paw Paw, MI 49079 Phone: (269) 628-2474 Email: mamenck@mei.net

Portage Creek Area Time Critical Removal Action EOM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Contact: Mary Ann Menck

Contact: Bill Schneider

Page 2

Special Native Seed Mixes

Midwestern Short Stature Prairie Seed Mix (DP3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientif	ie Name	Cor	mm	on	Name
	Grasses, Sedges	, and Rushes			
T	42 7 3	69.7.3	-		alma a

Bouteloua curtipendula Side Oats Grama Carex bicknellii Bicknell's Sedge Elymus virginicus Virginia Wild Rve Schizachyrium scoparium Little Bluestem Sporobolus heterolepis Prairie Dropseed

Forbs

Asclepias syriaca Common Milkweed Asclepias tuberosa Butterfly Milkweed Aster ericoides White Heath Aster Coreopsis lanceolata Sand Coreopsis Corcopsis palmata Prairie Coreopsis Echinacea purpurea Purple Coneflower Fringe-top Bottle Gentian Gentiana andrewsii Helianthus occidentalis Few-leaf Sunflower Lespedeza capitata Round-headed Bushclover Liatris aspeca Rough Blazingstar Liatris scariosa nieuwlandii Savanna Blazinestar Lupinus perennis Wild Blue Lupine Parthenium integrifolium Wild Quinine Foxglove Beard Tongue Penstemon digitalis Purple Prairie Clover Petalostemum purpureum Potentilla arguta Tall Cinquefoil Pycnanthemum virginianum Mountain Mint Rudbuckia fulgida Showy Black-eyed Susan Rudbeckia hirta Black-eyed Susan Solidago nemoralis Gray Goldenrod Tradescantia obiensis Ohio Spiderwort Hoary Vervain Verbena stricta Golden Alexanders Zizia aurea

Temporary Cover Grasses

Avena sativa Seed Oats

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture. D.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of E. composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be fine graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page 3

windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions. The entire surface shall be finished to provide positive drainage.

3.02 SEEDING & FERTILIZING

- Contractor shall sew seed and fertilize all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed and fertilizer shall be applied to all General Repair Areas and Spoil Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the General Repair Areas and Stockpile Areas.
 - a. Seed at 350 pounds per acre
 - b. Fertilize at 500 pounds per acre of 12-12-12

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil crosion control products, including (but not limited to) silt fence, crosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Price and Company, Inc. 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

- Minimum Erosion Control Products (as specified on the drawings).
 - DS75 Degradable Single Net Straw Blankets (100% biodegradable).
 - Propex 4553 Non-woven Geotextile Fabric
 - 3. Ecolofence 24 Silt Fence

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

- E. Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- F. All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

A. Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of I-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- A. It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- B. Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

ER

EQM CONTACT

Environmental Quality Management 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-309-4703 Mr. Jeff Rhinefield

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave, Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.







KALAMAZOO COUNTY, MICHIGAN

Site

Location

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA-6

INDEX OF DRAWING SHEETS

- Cover Sheet
- Site SA-6 Vegetation Plan
- **Detail Drawings**
- 4-6 Specifications



SITE LOCATION MAP

Know what's below. Call before you dig.

1-800-482-7171

ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT.

NOTE TO CONTRACTOR: 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL
- SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE


GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. No permitting is required for conducting re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.

CITY OF KALAMAZOO

http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan.

SER SASSOCIATES 536.1 ENVIRONMENTAL SCIENCE & ENGINEERING ph: (2)



- SPACING 6' MAX. -

SILT FENCE A

SILT FENCE B

RUBBER HOSE AT CONTACT POINTS

TWICE RADIUS OF ROOT BALL

4" MINIMUM PINE STRAW OR BARK MULCH

6" ANCHOR TRENCH





536 E. MICHIGAN AVE., SUITE 300 KALAMAZOO, MI 49007 ph: (269) 344-7117 fax: (269) 344-2493

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, TOWARDS DISTURBED SOILS.

WRAPPED AROUND FENCE POST FENCE JOINT

SECTION VIEW

SILT FENCE A

SHEET FLOW

FABRIC TO BE

UNDISTURBED SOILS

SOIL EROSION CONTROL GEOTEXTILE SILT FENCE

1<u>' MIN.</u>

FRONT VIEW

FENCE POSTS DRIVEN INTO GROUND 1' MIN.

. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER PINNING. OVERLAP TO BE SHINGLED WITH DIRECTION OF CREEK FLOW

I. THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.

PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF FERTILIZER AND

WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 9° OVERLAP, STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART.

BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.

LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.

EROSION CONTROL BLANKET DETAIL NO SCALE

ALLOW THIN LAYER OF SOIL TO COVER BALL BERM SIZE TO BE PROMINENT COMPACT OUTER EDGE WITH FOOTPRIN

> BACK FILL 1 PART COMPOST WITH 5 PARTS EXISTING SOIL - COMPACT BACK FILL IN BOTTOM OF HOLE

STAKING AND PLANTING TREE DETAIL

ALLOW THIN LAYER OF SOIL TO COVER BALL ROOT BALL TO BE 1/3 - 1/2 ABOVE EXISTING GRADE TWICE RADIUS BASED ON SOIL DRAINAGE IMPORTED TOP SOIL PEEL BACK BURLAP ON B&B SHRUBS - BACKFILL 1 PART COMPOSTED BARK WITH 5 PARTS EXISTING SOIL - COMPACT BACKFILL IN BOTTOM OF HOLE

> SHRUB DETAIL CONTAINER AND B&B


DIRECTION OF FLOW

NOILES:

1. ON-CENTER PLANT SPACING INDICATED IN GROUNDCOVER SCHEDULE (SHEET 9).

2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

<u>PLAN</u>



PLANTING GROUNDCOVER - NO SCALE

SA-6 VEGETATION

PART 1. GENERAL

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation. A.
- Seeding and fertilizing.
- C. Seed protection on slopes.
- D. Hydroseeding.
- Planting special seed mixes
 - 1. DP-3 (Midwestern Short Stature Prairie Seed Mix)
- Maintenance and Warrantee. F.

1.02 SUBMITTALS

- Documentation must include the following:
 - Submit seed tags to Engineer prior to seeding.
 - Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.
- Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Topsoil
 - Existing topsoil shall be re-used.
 - Import additional topsoil as needed.
- Water
 - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

SEED MIXTURE

Type "A" Seed Mixture (Repair of General Lawn Areas)

Portage Creek Area Time Critical Removal Action

EOM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page I

25 % Famous Kentucky Bluegrass Baron Kentucky Bluegrass Secretariat Perennial Ryegrass Boreal Creeping Red Fescue

All special native seed mixes shall be purchased from the following supplier:

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Trish Hacker-Henning

Contact: Cheryl Tolley

1) Heartland Restoration Services, Inc.

14921 Hand Road

Fort Wayne, Indiana 46818 Ph; (260) 489-8511

Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery Contact: Chad Hughson

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road

Rockford, MI 49341-7954 Ph: (616) 691-8214

Fax: (616) 691-7872 Email: cherylt@iserv.net

6) Mary Ann's Michigan Trees & Shrubs

28092 M-40 Hwv. Paw Paw, MI 49079 Phone: (269) 628-2474 Email: mamenck@mei.net

Portage Creek Area Time Critical Removal Action

FQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Contact: Mary Ann Menck

Page 2

windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions. The entire surface shall be finished to provide positive drainage.

3.02 SEEDING & FERTILIZING

- Contractor shall sew seed and fertilize all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed and fertilizer shall be applied to all General Repair Areas and Spoil Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the General Repair Areas and Stockpile Areas.
 - a. Seed at 350 pounds per acre
 - b. Fertilize at 500 pounds per acre of 12-12-12

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Price and Company, Inc.

425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. DS75 Degradable Single Net Straw Blankets (100% biodegradable).

KIESER & ASSOCIATES, LLC

- 2. Propex 4553 Non-woven Geotextile Fabric
- Ecolofence 24 Silt Fence

Portage Creek Area Time Critical Removal Action

FOM Project Number: 030281.0087 Specifications 02920

Special Native Seed Mixes

Midwestern Short Stature Prairie Seed Mix (DP3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientific Name Common Name Grasses, Sedges, and Rushes Bouteloua curtipendula Side Oats Grama Carex bicknellii Bicknell's Sedge Virginia Wild Rye Elymus virginicus

Little Bluestem Schizachyrium scoparium Sporobolus heterolepis Prairie Dropseed

Forbs Common Milkweed Asclepias syriaca Asclepias tuberosa Butterfly Milkweed Aster ericoides White Heath Aster Coreopsis lanceolata Sand Coreopsis Corcopsis palmata Prairie Coreopsis Echinacea purpurea Purple Coneflower Gentiana andrewsii Fringe-top Bottle Gentian Helianthus occidentalis Few-leaf Sunflower Round-headed Bushclover Lespedeza capitata Liatris aspera Rough Blazingstar Liatris scariosa nieuwlandii Savanna Blazingstar Lupinus perennis Wild Blue Lupine Parthenium integrifolium Wild Oumine Penstemon digitalis Foxelove Beard Tongue Petalostemum purpureum Purple Prairie Clover Potentilla arguta Tall Cinquefoil Pycnanthemum virginianum Mountain Mint Rudbuckia fulgida Showy Black-eyed Susan Rudbeckia hirta Black-cycd Susan Gray Goldenrod Solidago nemoralis Tradescantia ohiensis Ohio Spiderwort Verbena stricta Hoary Vervain

Temporary Cover Grasses

Avena sativa Seed Oats

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture. D.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

Golden Alexanders

PART 3. EXECUTION

SEEDBED PREPARATION 3.01

Zizia aurea

Within all disturbed Project Areas, the surface of the topsoil shall be fine graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All

Portage Creek Area Time Critical Removal Action

EQM Project Number: 030281,0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page 3

Page 4

SER

Portage Creek Area Time Critical Removal Action KALAMAZOO, MI EQM Project Number: 030281.0087

- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

536 E. MICHIGAN AVE., SUITE 300 KALAMAZOO, MI 49007 ph: (269) 344-7117 fax: (269) 344-2493

SER

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087


ER


S

EQM CONTACT

Environmental Quality Management 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-309-4703 Mr. Jeff Rhinefield

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave. Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.









ESER ASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087 PORTAGE CREEK - SITE SA-7



SITE LOCATION MAP

CITY OF KALAMAZOO

http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan,



Know what's below. Call before you dig.

1-800-482-7171

NOTES:
ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT. DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT.

NOTE TO CONTRACTOR: 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

INDEX OF DRAWING SHEETS


- **Cover Sheet**
- Site SA-7 Vegetation Plan (North)
- Site SA-7 Vegetation Plan (South) 3
- 4 **Detail Drawings**
- 5-7 Specifications

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL.
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. No permitting is required for conducting re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.



TREES TO BE 1" CALIPER, 4-6' TALL, BALLED/BURLAP

Clinton Ave.

QTY.

0.36

0.36

1

6

11

UNIT

AC

AC

EΑ

EΑ

EΑ

EΑ

EΑ

EΑ

MATCHLINE - (SHEET 2)

SWAMP ROSE *

MATCHLINE - (SHEET 3)

Egleston Ave.

QUANTITIES (THIS SHEET)

ITEM DESCRIPTION

SOIL ROUGHENING/SCARIFICATION

NATIVE SEED MIX (WP-3)

COMMON NINEBARK 💃

SWAMP WHITE OAK

RED MAPLE 🎉

SPICEBUSH *

SYCAMORE

3

Portage

Creek

SA-7 16 32

WORK LIMITS


762

TEMP. ACCESS PATH (FROM-

REED AVE.)

Reed

FULL SCALE: 1'' = 25'



Reed Ave.

 Ξ

NOTES:
1. ON-CENTER PLANT SPACING INDICATED IN GROUNDCOVER SCHEDULE (SHEET 9).

2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE

<u>Plan</u>

PLANT SPACING AS PER PLAN


- EROSION BLANKET INSTALLED BEFORE PLANTING


PREVIOUS GROWING LEVEL AT FINISH GRADE

5 PLANTING


PROFILE

4 GROUNDCOVER - NO SCALE





TREE DETAIL





ER

SA-7 VEGETATION

PART 1. GENERAL

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation. A.
- Seeding and fertilizing. В.
- C. Seed protection on slopes.
- D. Hydroseeding.
- E. Planting special seed mixes
 - 1. WP-3 (Midwestern Wet Prairie Seed Mix)
- F. Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - 1. Submit seed tags to Engineer prior to seeding.
 - Submit copy of invoice to media amendment.

1.03 OUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.
- Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions. A.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Topsoil A.
 - Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed.
- Water В.
 - 1. To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

2.03 SEED MIXTURE

Type "A" Seed Mixture (Repair of General Lawn Areas)

Portage Creek Area Time Critical Removal Action

EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Famous Kentucky Bluegrass Baron Kentucky Bluegrass Secretariat Perennial Ryegrass Boreal Creeping Red Fescue

All special native seed mixes shall be purchased from the following supplier:

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Trish Hacker-Henning

Contact: Cheryl Tolley

Contact: Mary Ann Menck

1) Heartland Restoration Services, Inc.

14921 Hand Road

Fort Wayne, Indiana 46818

Ph: (260) 489-8511 Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery Contact: Chad Hughson

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

Ortonville, MI 48462

1958 Hidden Lake Trail

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954

Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

6) Mary Ann's Michigan Trees & Shrubs

28092 M-40 Hwv. Paw Paw, MI 49079 Phone: (269) 628-2474

Email: mamenck@mei.net

Portage Creek Area Time Critical Removal Action

EQM Project Number: 030281.0087

Specifications 02920

Special Native Seed Mixes

Midwestern Wet Prairie Seed Mix (WP3)

Approximate mix weight 39 lb/acre, with 76 native seeds/sq. ft. 45.9% Grasses/Sedges/Rushes; 42.9%, Forbs; 11.2% Temporary Cover Grasses

Prairie Cord Grass

Common Name		
Grasses, Sedges, and Rushes		
Big Bluestem		
Blue Joint Grass		
Meadow Sedge		
Spreading Oval Sedge		
Short's Sedge		
Stalk Grain Sedge		
Fox Sedge		
Canada Wild Ryc		
Virginia Wild Rye		
Soft Rush		
Switch Grass		
Dark Green Bulrush		
Woolgrass		
Drooping Bulrush		

Forbs

Spartina pectinata

1.0103	
Asclepias incarnata	Marsh Milkweed
Aster firmus	Swamp Aster
Aster novae-angliae	New England Aster
Aster umbellatus	Flat-top White Aster
Eupatorium maculatum	Spotted Joe Pye Weed
Eupatorium perfoliatum	Common Boneset
Gentiana andrewsii	Fringe-top Bottle Gentian
Helenium autumnale	Common Sneezeweed
Liatris spicata	Spiked Gayfeather
Lobelia cardinalis	Cardinal Flower
Lobelia siphilitica	Great Blue Lobelia
Penstemon digitalis	Foxglove Beard Tongue
Pycnanthemum virginianum	Mountain Mint
Rudbeckia fulgida	Showy Black-eyed Susan
Rudbeckia triloba	Brown-eyed Susan
Senna hebecarpa	Wild Senna
Silphium perfoliatum	Cup Plant
Solidago riddellii	Riddell's Goldenrod
Tradescantia ohiensis	Ohio Spiderwort
Verbena hastata	Blue Vervain
Vernonia gigantea	Tall Ironweed
Veronicastrum virginicum	Culver's Root
Zizia aurea	Golden Alexanders

Page 3

Temporary Cover Grasses

Avena sativa Seed Oats

Portage Creek Area Time Critical Removal Action

EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be fine graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions. The entire surface shall be finished to provide positive drainage.

3.02 SEEDING & FERTILIZING

- Contractor shall sew seed and fertilize all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed and fertilizer shall be applied to all General Repair Areas and Spoil Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the General Repair Areas and Stockpile Areas.
 - a. Seed at 350 pounds per acre
 - b. Fertilize at 500 pounds per acre of 12-12-12

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Price and Company, Inc. 425 36th Street SW

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

Page 4

Portage Creek Area Time Critical Removal Action KALAMAZOO, MI
EQM Project Number: 030281.0087

536 E. MICHIGAN AVE., SUITE 300 KALAMAZOO, MI 49007 ph: (269) 344-7117 fax: (269) 344-2493

Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. DS75 Degradable Single Net Straw Blankets (100% biodegradable).
 - 2. Propex 4553 Non-woven Geotextile Fabric
 - 3. Ecolofence 24 Silt Fence
- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- All temporary crosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

ER

EQM CONTACT **Environmental Quality Management** 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-265-8875 Mr. Eric Bowman

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave. Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.







ESER ASSOCIATES ENVIRONMENTAL SCIENCE & ENGINEERING

PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA- I B



- **Cover Sheet**
- Site SA-1B Vegetation Plan
- **Detail Drawings**
- Specifications

o Ave 94 SA-1B **PROJECT AREA** 43

SITE LOCATION MAP

CITY OF KALAMAZOO http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w, SE 1/4 of Section 22 in Kalamazoo County, Michigan.



Know what's **below**. Call before you dig.

1-800-482-7171

NOTES: ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS DO NOT ASSUME THESE ARE THE ONLY UTILITIES PRESENT

3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".


EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION.
- 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE

GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. With EPA oversight, Contractor is not required to obtain permits for re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.





- SPACING 6' MAX. -

SILT FENCE A

SILT FENCE B 7

6" ANCHOR TRENCH

ER S

Portage Creek Area Time Critical Removal Action KALAMAZOO, MI EQM Project Number: 030281.0087 PORTAGE CREEK SITE 5A-1B

PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF SEED.

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER PINNING.

4. THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.

5. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 6" OVERLAP, STAPLE THROUGH OVERLAPPED AREA. APPROXIMATELY 12" APART.

BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.

LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.

NOTES:
1. ON-CENTER PLANT SPACING INDICATED ON PLANTING PLAN. 2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

PLAN

PLANT SPACING AS PER PLAN

- EROSION BLANKET INSTALLED BEFORE PLANTING

PREVIOUS GROWING LEVEL AT FINISH GRADE

PROFILE

PLANTING

GROUNDCOVER - NO SCALE

SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE

OVERLAP TO BE SHINGLED WITH DIRECTION OF CREEK FLOW DIRECTION OF FLOW

SOIL EROSION CONTROL GEOTEXTILE SILT FENCE

FENCE POSTS DRIVEN INTO GROUND 1' MIN.-

1' MIN.

FRONT VIEW

UNDISTURBED SOILS

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, ' TOWARDS DISTURBED SOILS.

COMPACT ANCHOR TRENCH

FABRIC TO BE WRAPPED AROUND FENCE POST

SHEET FLOW

SILT FENCE A


FENCE B

FENCE JOINT

EROSION CONTROL BLANKET DETAIL NO SCALE

RUBBER HOSE AT CONTACT POINTS TWICE RADIUS OF ROOT BALL 4" MINIMUM PINE STRAW BERM SIZE TO BE PROMINENT COMPACT OUTER EDGE WITH FOOTPRINT GROUND TREATED STAKES
(3 STAKES SPACED EQUIDISTANT) PEEL BACK BURLAP BACK FILL 1 PART COMPOST WITH 5 PARTS EXISTING SOIL - COMPACT BACK FILL IN BOTTOM OF HOLE STAKING AND PLANTING

TREE DETAIL NO SCALE





NO SCALE

SA-1B VEGETATION

PART 1. GENERAL

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding.
- C. Seed protection on slopes.
- Planting special seed mixes. D.
 - 1. DP-3 (Short Stature Prairie Seed Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - Submit seed tags to Engineer prior to seeding.
 - 2. Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.

EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

GROWING MEDIA 2.01

- Topsoil
 - Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed to minimize weed seed viability.

1. To be furnished by the Contractor. Portage Creek is an acceptable source.

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

Page I

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

2.03 SEED MIXTURE

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel

Contact: Bill Schneider

Contact: Chad Hughson

Contact: Cheryl Tolley

Contact: Randy Counterman

KIESER & ASSOCIATES, LLC

Contact: Trish Hacker-Henning

14921 Hand Road

Fort Wayne, Indiana 46818

Ph: (260) 489-8511

Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140

Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery

18 N Van Kal Street Kalamazoo, MI 49009 Ph; (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872

Email: cherylt@iserv.net

6) Native Landscapes

28092 M-40 Hwy. Paw Paw, MI 49079 Phone: 269-929-3455

Email: randy.counterman@gmail.com

EQM Project Number: 030281.0087

Page 2

Portage Creek Area Time Critical Removal Action Specifications 02920

SER

Special Native Seed Mixes

Midwestern Short Stature Prairie Seed Mix (DP-3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Scientific Name	Common Name
Grasses, Sedges, and	Rushes
Bouteloua curtipendula	Side Oats Grama
Carex bicknellii	Bicknell's Sedge
Elymus virginicus	Virginia Wild Rye
Schizachyrium scoparium	Little Bluestem
Sporobolus heterolepis	Prairie Dropseed

Faceboo

Common Milkweed
Butterfly Milkweed
White Heath Aster
Sand Coreopsis
Prairie Corcopsis
Purple Coneflower
Fringe-top Bottle Gentian
Few-leaf Sunflower
Round-headed Bushclover
Rough Blazingstar
Savanna Blazingstar
Wild Blue Lupine
Wild Quinine
Foxglove Beard Tongue
Purple Prairie Clover
Tall Cinquefoil
Mountain Mint
Showy Black-eyed Susan
Black-eyed Susan
Gray Goldenrod
Ohio Spiderwort
Hoary Vervain
Golden Alexanders

Temporary Cover Grasses

Avena sativa Seed Oats

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

3.01 SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be rough graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions.

3.02 SEEDING & FERTILIZING

- Contractor shall broadcast seed all topsoiled restoration areas at the rates recommended by the seed supplier for each type of native seed mix specified.
- Seed shall be applied to all Repair Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the Repair

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets, The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Hanes Geo Components 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230

Fx: (616) 530-2317

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

KIESER & ASSOCIATES, LLC

Contact: Mark Cavanaugh

Page 4

Page 3

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. Straw Single Net Erosion Blankets (100% biodegradable).
 - 2. TerraTex HPG-44 Geotextile Fabric
 - 3. Ecolofence 24" Silt Fence
- E. Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.
- F. All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

A. Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- A. It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of 1-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- B. Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS

Site

Location


KALAMAZOO COUNTY, MICHIGAN

S

EQM CONTACT

Environmental Quality Management 18000 Carillon Boulevard Cincinnati, OH 45240 (513)-265-8875 Mr Eric Bowman

CONSULTANT CONTACT KIESER & ASSOCIATES, LLC 536 E. Mich. Ave, Ste 300 Kalamazoo, MI 49007 (269) 344-7117 Mr. Brian Boyer, P.E.








PORTAGE CREEK TIME CRITICAL REMOVAL ACTION KALAMAZOO, MICHIGAN

EQM PROJECT NUMBER 030281.0087

PORTAGE CREEK - SITE SA-3A

INDEX OF DRAWING SHEETS

- **Cover Sheet**
- Site SA-3A Vegetation Plan
- **Detail Drawings**
- Specifications



SITE LOCATION MAP

CITY OF KALAMAZOO

http://www.kalamazoocity.org/onlinegis/CXviewer.htm T2s R11w. SE 1/4 of Section 22 in Kalamazoo County, Michigan.



Know what's **below**. Call before you dig. 1-800-482-7171

<u>NOTES:</u> ALL EXISTING UTILITY LOCATIONS DEPICTED ON THESE PLANS ARE APPROXIMATE; BASED ON AVAILABLE INFORMATION AND FIELD OBSERVATIONS BY OTHERS. AS A RESULT, UTILITY LOCATIONS SHOWN ARE NOT EXACT.

NOTE TO CONTRACTOR: 3 FULL WORKING DAYS BEFORE YOU DIG, CALL "MISS DIG".

EROSION CONTROLS

- 1. ALL CONSTRUCTION SHALL COMPLY WITH THE SOIL EROSION AND SEDIMENTATION CONTROL ACT (P.A. 347 OF 1972, AS AMENDED).
- 2. ALL TEMPORARY EROSION CONTROLS SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO COMMENCING WORK, TO THE EXTENT POSSIBLE.
- 4. CONTRACTOR TO PROTECT ONSITE CATCH BASINS FROM DAMAGE AND SEDIMENTATION. 5. ENSURE PROPER DRAINAGE FOLLOWING BACKFILL
- 6. CONTRACTOR SHALL MONITOR AND MAINTAIN ALL SOIL EROSION CONTROL MEASURES FOR THE DURATION OF THE CONSTRUCTION PERIOD.
- 7. SUPPLEMENTAL SOIL EROSION CONTROLS SHALL BE INSTALLED AS NEEDED TO ENSURE


GENERAL NOTES:

- 1. The Contractor is responsible for contacting MISS DIG (1-800-482-7171) at least 3 working days before construction begins. The Contractor shall provide the MISS DIG ticket number upon request. Any utility conflicts must be presented to the Engineer in writing prior to commencement of work.
- 2. No permitting is required for conducting re-vegetation work.
- 3. The Contractor is responsible for knowing and following all appropriate safety standards which are required by the Michigan Occupational Safety and Health Act.
- 4. Hard hats must be worn by anyone on the site who may be exposed to falling objects or flying debris and anyone within the operating range of overhead construction equipment. This equipment includes, but is not limited to, backhoes, cranes, draglines, and front end loaders.
- 5. Any deviation from these construction drawings and specifications will be considered defective work, subject to modification for conformance at the Contractor's expense.
- 6. Contractor shall keep disturbance of all areas of construction to a minimum.
- 7. Locations and elevations of existing utilities are not exact. Contact Miss Dig at 1-800-482-7171, prior to beginning construction.
- 8. Existing utilities destroyed or disturbed by the Contractor's operations shall be repaired at the Contractor's expense.
- 9. Hand dig in all areas of existing utilities.
- 10. The contractor shall be required to prevent movement of soil off site. Additional silt fencing may be required beyond that already on-site. Any additional silt fencing shall be incidental to work.
- 11. All work shall be checked for accuracy to the plans by the Contractor prior to installation.

FULL SCALE: 1" = 100'



INSTALL MULCH EROSION BLANKETS



ECOLOFENCE 24 BY PRICE & COMPANY

- SPACING 6' MAX.

SILT FENCE A

SILT FENCE B

6" ANCHOR TRENCH

FENCE POSTS DRIVEN INTO GROUND 1' MIN.-

1' MIN.

SOIL EROSION CONTROL

GEOTEXTILE SILT FENCE

FRONT VIEW

SOCL S

ER

S

Portage Creek Area Time Critical Removal Action
KALAMAZOO, MI
EQM Project Number: 030281.0087
PORTAGE CREEK SITE 5A-3A

OVERLAP TO BE SHINGLED WITH DIRECTION OF CREEK FLOW

THE EDGES OF PARALLEL BLANKETS MUST BE PINNED WITH APPROXIMATELY 2" OVERLAP.

NOTES:

. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 6° OVERLAP, STAPLE THROUGH OVERLAPPED AREA APPROXIMATELY 12" APART.

PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF FERTILIZER AND

. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP BY 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER PINNING.

BLANKETS SHALL BE PINNED IN ROWS NOT MORE THAN 2 FT O.C. WITH A MAXIMUM OF 20" BETWEEN PINS, 3.5 PINS PER SQ YD.

LOWER END OF BLANKET TO BE TUCKED 6" MIN. BELOW EDGE OF TOE.

NOTES:

1. ON-CENTER PLANT SPACING INDICATED IN GROUNDCOVER SCHEDULE (SHEET 9).

2. ALL PLUG MATERIALS SHALL BE TRUE TYPE AND NAME.

SET PLANT VERTICALLY NOT PERPENDICULAR TO SLOPE

<u>PLAN</u>

- EROSION BLANKET INSTALLED BEFORE PLANTING

PREVIOUS GROWING LEVEL AT FINISH GRADE

PROFILE

PLANTING

GROUNDCOVER - NO SCALE

DIRECTION OF FLOW

TWICE RADIUS
OF BALL

GEOTEXTILE FILTER FABRIC FACING UPHILL SIDE, TOWARDS DISTURBED SOILS.

COMPACT ANCHOR TRENCH

ON UPHILL SIDE OF

SHEET FLOW

ANCHOR TRENCH

FABRIC TO BE WRAPPED AROUND FENCE POST

UNDISTURBED SOILS

FENCE B

FENCE JOINT

EROSION CONTROL BLANKET DETAIL

NO SCALE

ALLOW THIN LAYER OF SOIL TO COVER BALL

ROOT BALL TO BE 1/3 - 1/2 ABOVE EXISTING GRADE BASED ON SOIL DRAINAGE

IMPORTED TOP SOIL

- PEEL BACK BURLAP ON B&B SHRUBS

BACKFILL 1 PART COMPOSTED BARK WITH 5 PARTS EXISTING SOIL

RUBBER HOSE AT CONTACT POINTS TWICE RADIUS OF ROOT BALL 4" MINIMUM PINE STRAW OR BARK MULCH— BERM SIZE TO BE PROMINENT COMPACT OUTER EDGE WITH FOOTPRIN GROUND TREATED STAKES
(3 STAKES SPACED EQUIDISTANT) PEEL BACK BURLAP - COMPACT BACK FILL IN BOTTOM OF HOLE

STAKING AND PLANTING

TREE DETAIL

4" MINIMUM PINE STRAW OR BARK MULCH ——— SHRUB DETAIL

CONTAINER AND B&B NO SCALE

S

ER

S

SA-3A VEGETATION

PART 1. GENERAL

1.01 SECTION INCLUDES

- Preparation of grades to receive seeding and vegetation.
- Seeding and fertilizing.
- C. Seed protection on slopes.
- D. Hydroseeding.
- Planting special seed mixes
 - 1. DP-3 (Short Stature Prairie Seed Mix)
 - 2. WS-2 (Riparian Mix)
 - 3. WP-7 (Short Stature Bioswale Mix)
- Maintenance and Warrantee.

1.02 SUBMITTALS

- Documentation must include the following:
 - 1. Submit seed tags to Engineer prior to seeding.
 - Submit copy of invoice to media amendment.

1.03 QUALITY ASSURANCE

Grass seed shall meet the tolerance for germination and purity of the Official Seed A. Analyses of North America.

1.04 PRODUCT DELIVERY, STORAGE, AND HANDLING

- Deliver seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of testing, and location of packaging. Damaged packages are not acceptable.
- Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer.

1.05 EXISTING CONDITIONS

Beginning work means acceptance of existing conditions.

PART 2. PRODUCTS

2.01 GROWING MEDIA

- Topsoil
 - Existing topsoil shall be re-used.
 - 2. Import additional topsoil as needed.
- - To be furnished by the Contractor. Portage Creek is an acceptable source.

2.02 SEED

Seed shall be new crop, cleaned, and comprising of the following varieties mixed in proportion by weight shown and testing the minimum percentages and germination indicated as follows:

Page I

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

2.03 SEED MIXTURE

Type "A" Seed Mixture (Repair of General Lawn Areas)

25 % Famous Kentucky Bluegrass Baron Kentucky Bluegrass Secretariat Perennial Ryegrass Boreal Creeping Red Fescue

All special native seed mixes shall be purchased from the following supplier:

1) Heartland Restoration Services, Inc.

Contact: Eric Ummel 14921 Hand Road

Fort Wayne, Indiana 46818 Ph: (260) 489-8511 Fx: (260) 489-8607

Email: mail@earthsourceinc.net

Trees, shrubs and plugs (refer to tree/shrub schedule on the drawings) shall be purchased from the following supplier(s) to the extent possible (as current stock allows):

2) Wildtype Native Plant Nursery

900 N. Every Road Mason, MI 48854 Ph: (517) 244-1140 Fax: (517) 244-1142 E-mail: wildtype@msu.edu

3) Hidden Savanna Nursery

18 N Van Kal Street Kalamazoo, MI 49009 Ph: (269)352-3876

Email: info@hiddensavanna.com

4) American Roots

1958 Hidden Lake Trail Ortonville, MI 48462

Ph: (248) 627-8525 or (248) 882-7768

Fax: (248) 627-3865

Email: americanrootsnat@aol.com

5) Sandhill Farm

11250 10 Mile Road Rockford, MI 49341-7954 Ph: (616) 691-8214 Fax: (616) 691-7872 Email: cherylt@iserv.net

Contact: Cheryl Tolley

Contact: Bill Schneider

Contact: Chad Hughson

Contact: Trish Hacker-Henning

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

S

ER

S

6) Mary Ann's Michigan Trees & Shrubs

28092 M-40 Hwy. Paw Paw, MI 49079 Phone: (269) 628-2474 Email: mamenek@mei.net

Special Native Seed Mixes C.

Midwestern Short Stature Prairie Seed Mix (DP-3)

Approximate mix weight 43 lb/acre with 74 native seeds/sq.ft. 44.4% Grasses/Sedges/Rushes; 44.1% Forbs; 11.4% Temporary Cover Grasses

Contact: Mary Ann Menck

Scientifie Name	Common Name
Grasses, Sedges,	and Rushes
Routelous curtinendula	Side Oats Grama

Bicknell's Sedge Carex bicknellii Elymus virginicus Virginia Wild Rye Schizachyrium scoparium Little Bluestem Sporobolus heterolepis Prairie Dropseed

Forbs

Asclepias syriaca Common Milkweed Asclepias tuberosa Butterfly Milkweed Aster ericoides White Heath Aster Coreopsis lanceolata Sand Coreopsis Coreopsis palmata Prairie Coreopsis Purple Coneflower Echinacea purpurea Fringe-top Bottle Gentian Gentiana andrewsii Helianthus occidentalis Few-leaf Sunflower Lespedeza capitata Round-headed Bushclover Rough Blazingstar Liatris aspera Liatris scariosa nieuwlandii Savanna Blazingstar Lupinus perennis Wild Blue Lupine Parthenium integrifolium Wild Quinine Penstemon digitalis Foxglove Beard Tongue Petalostemum purpureum Purple Prairie Clover Potentilla arguta Tall Cinquefoil Pycnanthemum virginianum Mountain Mint Rudbuckia fulgida Showy Black-eyed Susan Rudbeckia hirta Black-eyed Susan Solidago nemoralis Grav Goldenrod Ohio Spiderwort Tradescantia ohiensis Hoary Vervain Verbena stricta

Temporary Cover Grasses

Avena sativa Seed Oats

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Zizia aurea

Specifications 02920

KIESER & ASSOCIATES, LLC

2) Midwestern Riparian Seed Mix (WS-2)

Approximate mix weight 73 lb/acre with 46 native seeds/sq. ft. 13.9% Grasses/Sedges/Rushes; 5.4% Forbs; 80.7% Temporary Cover Grasses

Golden Alexanders

Scientific Name Common Name Grasses, Sedges, and Rushes

Carex frankii Frank's Sedge Carex muskingumensis Palm Sedge

Carex normalis Spreading Oval Sedge Carex souarrosa Squarrose Sedge Carex vulpinoidea Fox Sedge

Cinna artindinacea Common Wood Reed Elymus canadensis Canada Wild Ryc Elymus riparius Riverbank Wild Rye Elymus virginicus Virginia Wild Rye Glyceria striata Fowl Manna Grass Leersia oryzoides Rice Cut Grass Switch Grass Panicum virgatum Scirpus atrovirens Dark Green Bulrush Scirpus pendulus Drooping Bulrush

Forbs

Aster novae-angliae New England Aster Bidens cerma Nodding Bur Marigold Eupatorium purpureum Purple Joe Pye Weed Eupatorium rugosum White Snakeroot Heliopsis helianthoides False Sunflower Lysimachia ciliata Fringed Loosestrife Rudbeckia laciniata Green-headed Coneflower Rudbeckia triloba Brown-eyed Susan Silphium perfoliatum Cup Plant Verbesina alternifolia Wingstem Vernonia gigantea Tall Ironweed

Temporary Cover Grasses

Agrostis alba Redtop Agrostis alba palustris

Creeping Bent Grass Avena satíva Seed Oats Lolium multiflorum Annual Ryc Grass

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087 Specifications 02920

Zizia aurea

KIESER & ASSOCIATES, LLC

Golden Alexanders

Page 3

Midwestern Short Stature Bioswale Seed Mix (WP-7)

Approximate mix weight 72 lb/acre, with 61 native seeds/sq. ft. 12.7% Grasses/Sedges/Rushes; 7.8% Forbs; 79.5% Temporary Cover Grasses

Scientific Name Common Name

Grasses, Sedges, and Rushes

Calamagrostis canadensis Blue Joint Grass Carex frankii Frank's Sedge Carex granularis Meadow Sedge Carex normalis Spreading Oval Sedge Carex shortiana Short's Sedge Carex stipata Stalk Grain Sedge Carex tribuloides Blunt Broom Sedge Carex vulpinoidea Fox Sedge Elymus virginicus Virginia Wild Rye Leersia oryzoides Rice Cut Grass

Forbs

Nodding Bur Marigold Bidens cernua Echinacea purpurea Purple Coneflower Euthamia graminifolia Flat-top Fragrant Goldenrod Fringe-top Bottle Gentian Gentiana andrewsii Lobelia siphilitica Great Blue Lobelia Penstemon digitalis Foxglove Beard Tongue Pycnanthemum virginianum Mountain Mint Rudbeckia fulgida Showy Black-eyed Susan Rudbeckia hirta Black-eved Susan Tradescaptia obiensis Ohio Spiderwort Verbena stricta Hoary Vervain Zizia aurea Golden Alexanders

Temporary Cover Grasses

Creeping Bent Grass Agrostis alba palustris Avena sativa Seed Oats Lolium multiflorum Annual Rye Grass

- Weed seed content shall not exceed 0.25 percent for any variety of seed mixture. D.
- Seed shall be mixed by the dealer. Furnish dealer's guaranteed statement of E. composition, mixture and percentages of purity, and germination of each variety.

PART 3. EXECUTION

SEEDBED PREPARATION

Within all disturbed Project Areas, the surface of the topsoil shall be fine graded and prepared for seeding by removing rocks and debris larger than 2-inch diameter. All windrows shall be eliminated. Hand raking shall be performed around all structures to form smooth transitions. The entire surface shall be finished to provide positive drainage.

3.02 SEEDING & FERTILIZING

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

- Contractor shall sew seed and fertilize all topsoiled restoration areas at the rates A. recommended by the seed supplier for each type of native seed mix specified.
- Seed and fertilizer shall be applied to all General Repair Areas and Spoil Areas at the approximate rates shown below. The Contractor shall submit a certified list of the actual seed percentages used in the General Repair Areas and Stockpile Areas.
 - a. Seed at 350 pounds per acre
 - b. Fertilize at 500 pounds per acre of 12-12-12

3.03 MULCHING & EROSION CONTROLS

- On the Project Areas receiving native seed mixes, the Contractor shall furnish and install mulch blankets at the locations and to the limits shown on the construction drawings. The mulch blanket shall be North American Green DS75 Straw Blankets. The Contractor shall install and anchor the mulch blankets with wood or metal stakes in accordance with the manufacturer's recommendations. Mechanical anchoring shall be performed in a manner that creates ridges perpendicular to flow of water. Where blankets are used in flow areas, the upstream end of each section shall be buried in a trench to a minimum depth of 6 inches. The Contractor shall water the mulch blanket areas at a rate of approximately 2,000 gallons per acre. Water may be obtained from the onsite creek.
- Shredded straw mulch shall be applied at a rate of 2 tons per acre on the adjacent disturbed general lawn areas and spoils fill areas. Shredded straw mulch shall only be applied when wind speeds are 5 mph or less, except if approved otherwise by the Owner. The shredded straw mulch shall be anchored with a sharp-edged "crimping tool". The crimping tool shall be capable of partially cutting, embedding and anchoring the straw so it will not be blown away. The entire surface of the mulched Project shall receive two passes of the crimping tool. The second pass shall be 90 degrees to the first, unless approved otherwise by the Owner.
- All soil erosion control products, including (but not limited to) silt fence, erosion control blankets, mulch netting, biostake anchoring pins, non-woven geotextile fabric, and coir logs shall be purchased from the following supplier:

Hanes Geo Components

Contact: Mark Cavanaugh 425 36th Street SW Wyoming, MI 49548 Ph: (616) 530-8230 Fx: (616) 530-2317

- Minimum Erosion Control Products (as specified on the drawings).
 - 1. Straw Single Net Erosion Blankets (100% biodegradable).
 - 2. TerraTex HPG-44 Geotextile Fabric
 - 3. Ecolofence 24" Silt Fence
- Additional erosion control measures shall be implemented as required to minimize silt or sediment leaving the construction site. The Contractor shall monitor and maintain all erosion control devices throughout the duration of the construction period.

Portage Creek Area Time Critical Removal Action EQM Project Number: 030281.0087

Specifications 02920

KIESER & ASSOCIATES, LLC

Page 6

SOCIA S SER

Page 5

(269) 344-2493 536 E. MICHIGAN AVE., SUITE 300 KALAMAZOO, MI 49007 ph: (269) 344-7117 fax: (269) 344-2493

All temporary erosion control devices should be in place prior to the start of construction/excavation activities, to the extent possible. The Contractor shall remove all temporary erosion control devices once full vegetation has been established.

3.04 MAINTENANCE

Maintenance responsibilities begin immediately upon completion of seeding and planting, and shall continue for a period of 1-year. All wind, water, fire, vandalism, or natural damage that occurs during this time frame shall be repaired by the Contractor within 5 days of being notified by EQM at no additional cost to the project. Repairs shall be completed in a manner that meets the requirements of these specifications.

3.05 GUARANTEE

- It is the responsibility of the Contractor to establish and maintain a dense growth of vegetation, for a period of I-year. All trees and shrubs shall be provided with a minimum 1-year warrantee. Institute measures to protect completed landscape areas. Any part of the area that fails to show a uniform germination shall be re-seeded and such re-seeding shall continue until a dense growth is established. The Contractor shall repair damage to seeded areas resulting from erosion and/or overwatering.
- Replace dead or unhealthy plants with plants of the same size and species as specified. Species substitutions will not be allowed without engineer approval.

END OF SPECIFICATIONS